MYRRHA QPLANT — Single Source of Truth (SSoT)

> **Version:** v0.4 · **Status:** IMMUTABLE design parameters (edit via truth.html Edit Mode)

B1 — Baseline Mass Flow

- **Target:** `350 g/s @ 14 barG`
- Reference operating point for HCC + LCC combined delivery.

B2 — ALaT Operating Point

- **Configuration:** 2 FSD (Full-Speed Drives)
- **Compressor model:** SFC 575
- **Speed:** 72 Hz
- **Delivery:** ~220 g/s

B3 — LKT Operating Point

- **Configuration:** 3 FSD
- **Compressor model:** SFC 475
- **Speed:** ~57 Hz
- **Delivery:** 264 g/s (nominal)

B4 — RCW (Recirculating Cooling Water)

- **Hot side max:** 85 °C
- **Inlet:** 30 °C
- **ΔT:** 25 °C

B5 — LCC / PVPS

- **Target:** 50 g/s
- **Units:** 2 × 5 = 10 total (N+1 redundancy)

Change Log

Version	Date	Field	Old → New	Author
v0.4	2026-05-10	(init)	— (initial SSoT)	system